

ILLEGIB

~~TOP SECRET~~ [REDACTED]

25X1

Declass Review by NIMA / DoD

NPIC/R-82/62

### ICBM LAUNCH COMPLEX, SVOBODNYY, USSR

25X1D The Svobodnyy ICBM Launch Complex, initially identified on [REDACTED]  
25X1D [REDACTED] is located 21.5 nautical miles  
(nm) north of Svobodnyy, USSR, and just east of the Trans-Siberian Rail-  
25X1D road. In [REDACTED] the complex consisted basically of a rail-served  
complex support facility and three road-served launch areas, in varying  
stages of construction (Figure 1).  
25X1D A search of existing photography revealed that in [REDACTED]  
25X1D [REDACTED] no unusual activity was evident at or near the present loca-  
tions of any of the complex facilities. The location of Launch Area C was  
25X1D observed on [REDACTED] but  
at that time there was no activity.

This ICBM complex is the easternmost site identified to date in the  
USSR. The only SAM defenses in the area are provided by four SA-2 sites  
that apparently defend Ukraina Airfield [REDACTED]  
[REDACTED] located south of Svobodnyy. No other  
SAM sites have been identified in the area.

25X1

### COMPLEX SUPPORT FACILITY AND NEARBY AREAS

The support facilities for the ICBM complex include the Complex  
Support Facility and four nearby areas: a rail-to-road transfer point, a  
large housing and administration area, and two areas of unidentified  
activity, one of which is secured. The rail spur serving the complex leaves  
the Trans-Siberian Railroad at Stantsiya Ledyanaya, 21.5 nm north of  
Svobodnyy, and goes northeast for 3 nm to the Rail-to-Road Transfer Point,  
where it terminates (Figure 2).

About 4,000 feet southwest of the Transfer Point, the spur branches  
northwest and enters the Complex Support Facility, which is located at  
51-46-20N 128-07-40E. This branch spur expands in this facility into

- 1 -

~~TOP SECRET~~ [REDACTED]

25

25X2

TOP SECRET

25X1

NPIC/R-82/62




FIGURE 2. COMPLEX SUPPORT FACILITY AND NEARBY AREAS.

- 3 -

TOP SECRET

2

**TOP SECRET**

25X1

NPIC/R-82/62

three rail spurs 3,100 feet long and 530 feet apart. The shortest rail turning radius is approximately 1,000 feet. The Complex Support Facility has 75 buildings and covers about 550 acres. Of the larger structures, 2 buildings are 220 by 90 feet, 4 are 180 by 90 feet, 4 are 180 by 60 feet, and 16 are 160 by 40 feet.

A large road-served housing and administration area is located 2.3 nm south-southwest of the Transfer Point. The area covers about 140 acres and contains over 100 apartment and administration-type buildings. A good road connects this area with the road serving other parts of the complex.

Immediately southeast of the rail line and across from the Complex Support Facility is an area of unidentified construction activity. It has a rectangular road pattern and contains two large probable buildings under construction, each measuring 310 by 130 feet, and a building 200 by 60 feet.

The Transfer Point is located at 51-46-20N 128-09-00E, at the terminus of the rail spur serving the complex. It consists of a wide-looping road with a turning radius of 150 feet. The road parallels the rail spur for 750 feet. At least four buildings, none of which have a rail-through capability, are located in the area. Two of these measure 120 by 60 feet and two measure 120 by 40 feet. From the Transfer Point a good road serves the three launch areas, all of which are within 15 nm by road.

About 2.7 nm east-northeast of the Transfer Point on the south side of the road which serves the launch areas is a secured area of unidentified activity (Figure 1). This road-served area, located at 51-47-40N 128-12-30E, covers 28 acres and is enclosed by a fence measuring 1,350 by 900 feet. Inside the fence line is unidentified scarring, possibly a shallow excavation. Along the short road serving the area and on the north side of the fence is a row of six buildings, each measuring 180 by 60 feet.

- 4 -

**TOP SECRET**

25X

TOP SECRET


25X1

NPIC/R-82/62

### LAUNCH AREA A

Launch Area A, the farthest advanced in construction of any of the launch areas at the Svobodnyy complex, is located in a forest at 51-55-00N 128-10-30E, 12.3 nm by road (8.9 nm straight-line distance) north of the Transfer Point. It appears to be in a late stage of construction and has two elongated launch pads 135 feet wide and 980 feet apart. Their long axis is oriented on an azimuth of approximately [ ] (Figure 3). The area is secured by a roughly rectangular fence measuring 2,300 by 2,000 feet which encloses 106 acres. The center service road between the pads is offset to the right. Two small structures, one of them a probable bunker, are positioned between the pads. Two missile-ready buildings, each 675 feet behind the center of the pad it serves, are evident. The right building is offset from the pad orientation and measures 180 by 135 feet. The left building, aligned with the left pad, measures 180 by 90 feet. About 3,000 feet south

25X1D



25X1D

FIGURE 3. LAUNCH AREA A

25X1D

- 5 -

TOP SECRET

25X1

TOP SECRET

25X1

NPIC/R-82/62

of the launch area is a launch support area containing two groups of buildings. One group has five buildings measuring 180 by 65 feet. The other group has 19 buildings; 12 of these measure 160 by 40 feet and the others are smaller.

#### LAUNCH AREA B

Launch Area B is located in a forest at 51-49-30N 128-19-10E, 10.5 nm by road (7.2 nm straight-line distance) east-northeast of the Transfer Point. This area is 7.5 nm southeast of Launch Area A and 4.7 nm southwest of Launch Area C. It covers 116 acres and is enclosed by a fence measuring 2,300 by 2,200 feet. The area is almost identical with Launch Area A except that it is in an earlier stage of construction and the center road between the pads is offset to the left (Figure 4). The two pads are elongated, 135 feet wide, and 990 feet apart. The long axis of each pad is oriented on an azimuth of approximately [ ] Structures usually found between the pads in ICBM launch areas are not visible here,

25X1D

25X1D




FIGURE 4. LAUNCH AREA B

- 6 -

25X1D

TOP SECRET

25X

TOP SECRET

25X1

NPIC/R-82/62

but extensive scarring indicates their probable construction. Two missile-ready buildings under construction are visible; each is 675 feet behind the center of its pad. The right building measures 180 by 135 feet and is offset to the right from the azimuth of the pads. The left building, aligned with the left pad, measures 180 by 90 feet.

A launch support area with three groups of buildings (one group not shown on Figure 4) is south of the launch area. One group has 4 buildings measuring 180 by 60 feet; the second, 8 buildings 180 by 40 feet; and the third, 4 buildings 160 by 40 feet.

#### LAUNCH AREA C

Launch Area C, in a very early stage of construction, is at 51-53-20N 128-23-40E, in a forest 15 nm by road (12.5 nm straight-line distance) northeast of the Transfer Point. At the time of the coverage, the area consisted of two shallow excavations 990 feet apart, with a center road offset to the right passing between them on an azimuth of approxi-

25X1D




FIGURE 5. LAUNCH AREA C

25X1D

TOP SECRET

25X

**TOP SECRET**

25X1

NPIC/R-82/62

25X1D mately  (Figure 5). A clearing 675 feet behind the left excavation indicates that the left missile-ready building will probable be offset when construction is completed. Figure 5 indicates the projected configuration of this launch area when completed. A launch support area is south-southwest of the excavations and at the time of photography had seven buildings measuring 160 by 40 feet.

— • —

REFERENCES

PHOTOGRAPHY

25X1D



MAPS OR CHARTS

SAC. US Air Target Chart, Series 200, Sheet 0203-3AL, 2d ed, Jun 60, scale 1:200,000 (SECRET)

REQUIREMENTS

CIA. DDI/RR/E/R-31/62

Air. AFIC 62-20

NPIC PROJECT

JN-92/62

**TOP SECRET**

25X1